


Summitliftco.net



FOR SALE

T-Bar Lift

This is an operating Doppelmayr Tbar that will be removed in the spring of 2009. It is in excellent condition and comes with a new haul rope still on the spool. Tensioning is hydraulic and the drive has step starting.



MODEL: 3P 680 EM

3.21 / 200
580
2320
2217
130

LIFT DATA (BETWEEN ~~C~~ BULLWHEELS - ENTRANCE SHEAVES)

INCLINED LENGTH	FT	807,07	M
HORIZONTAL LENGTH	FT	756,30	M
VERTICAL RISE	FT	281,80	M
AVERAGE GRADE	%	20,44	°
LIFT SPEED	FPM	2,86	M/S
CARRIER SPACING	FT	24,23	M
CARRIERS REQUIRED		69	
CARRIER INTERVALL	SEC	8,47	SEC
HOURLY CAPACITY (THEORET.)	P/H	850	P/H
TRIP TIME		4+48	MIN+SEC

HAUL ROPE:

DIA.	IN.	22	MM
CONSTRUCTION		6 x 19	
GRADE		1960	N/MM ²
BREAKING STRENGTH REQU'D	LBS	327,50	KN
SPLICED LENGTH	FT	1640,90	M

TENSIONING: WGT., HYDR.	LBS	121,74	KN
DRIVE HP-OUTPUT REQU'D	CONT.	HP	KW
	START	HP	KW

ELEVATION OF DRIVE TERMINAL A.S.L. FT 99,40 MUM

DIRECTION OF ROTATION CW-LEFT ~~CW-RIGHT~~

a	Rope Height Return Station changed (lowered by 10cm)	20-06-04	Ma
21. Index	Revisions	Date	Name

KOMM. NR. 73.S.590

DRAWN	Ma	YR	MO	DAY
		90	06	21

APPR.

SCALE 1:500

DRAWG. NR. S-45157-a





Price ex parking lot Jasper Alberta \$150,000.00 CAN